

Notice of Meeting

Planning Control Committee

Date: Tuesday 6 November 2018
Time: 5.30 pm
Venue: Main Hall, Crosfield Hall, Broadwater Road, Romsey, Hampshire,
SO51 8GL

For further information or enquiries please contact:

Sally Prior - 01264 368024
sprior@testvalley.gov.uk

Legal and Democratic Service

Test Valley Borough Council,
Beech Hurst, Weyhill Road,
Andover, Hampshire,
SP10 3AJ

www.testvalley.gov.uk

The recommendations contained in the Agenda are made by the Officer and these recommendations may or may not be accepted by the Committee.

PUBLIC PARTICIPATION SCHEME

If members of the public wish to address the meeting they should notify the Legal and Democratic Service at the Council's Beech Hurst office by noon on the working day before the meeting.

Membership of Planning Control Committee

MEMBER	WARD
Councillor J Budzynski (Chairman)	Andover (Winton)
Councillor J Neal (Vice-Chairman)	Andover (Millway)
Councillor G Bailey MBE	Blackwater
Councillor C Borg-Neal	Andover (Harroway)
Councillor P Boulton	Broughton & Stockbridge
Councillor P Bundy	Chilworth, Nursling & Rownhams
Councillor D Busk	Broughton & Stockbridge
Councillor M Cooper	Romsey (Tadburn)
Councillor A Dowden	Valley Park
Councillor C Dowden	North Baddesley
Councillor A Finlay	Chilworth, Nursling & Rownhams
Councillor M Hatley	Ampfield & Braishfield
Councillor S Hawke	Andover (Millway)
Councillor I Hibberd	Romsey Extra
Councillor J Lovell	Andover (Winton)
Councillor T Preston	Andover (Alamein)
Councillor I Richards	Romsey (Abbey)

Planning Control Committee

Tuesday 6 November 2018

AGENDA

The order of these items may change as a result of members of the public wishing to speak

- 1 Apologies**
- 2 Public Participation**
- 3 Declarations of Interest**
- 4 Urgent Items**
- 5 Minutes of the meeting held on 16 October 2018**
- 6 Information Notes 4 - 9**
- 7 18/01953/FULLS - 24.07.2018 10 - 46**

**(RECOMMENDATION OF SOUTHERN AREA
PLANNING COMMITTEE: REFUSE)
(RECOMMENDATION OF HEAD OF PLANNING AND
BUILDING: PERMISSION)**

SITE: Land adjacent to Meadow View, Houghton,
Stockbridge, SO20 6LT, **HOUGHTON**
CASE OFFICER: Ms Astrid Lynn

ITEM 6

TEST VALLEY BOROUGH COUNCIL

PLANNING CONTROL COMMITTEE

INFORMATION NOTES

Availability of Background Papers

Background papers may be inspected up to five working days before the date of the Committee meeting and for four years thereafter. Requests to inspect the background papers, most of which will be on the application file, should be made to the case officer named in the report or to the Development Manager. Although there is no legal provision for inspection of the application file before the report is placed on the agenda for the meeting, an earlier inspection may be agreed on application to the Head of Planning and Building.

Reasons for Committee Considerations

Applications are referred to the Planning Control Committee from the Northern or Southern Area Planning Committees where the Head of Planning and Building has advised that there is a possible conflict with policy, public interest or possible claim for costs against the Council.

The Planning Control Committee has the authority to determine those applications within policy or very exceptionally outwith policy and to recommend to the Cabinet and to the Overview and Scrutiny Committee revisions to policy resulting from its determination of applications.

Approximately 15% of all applications are determined by Committee. The others are determined by the Head of Planning and Building in accordance with the Council's Scheme of Delegation which is set out in the Council's Constitution.

Public Speaking at the Meeting

The Council has a public participation scheme, which invites members of the public, Parish Council representatives and applicants to address the Committee on applications. Full details of the scheme are available from Planning and Building Services or from the Committee Administrator at the Council Offices, Beech Hurst, Weyhill Road, Andover. Copies are usually sent to all those who have made representations. Anyone wishing to speak must book with the Committee Administrator within the stipulated time period otherwise they will not be allowed to address the Committee.

Speakers are limited to a total of three minutes per item for Councillors with prejudicial interests, three minutes for the Parish Council, three minutes for all objectors, three minutes for all supporters and three minutes for the applicant/agent. Where there are multiple supporters or multiple objectors wishing to speak the Chairman may limit individual speakers to less than three minutes with a view to accommodating multiple speakers within the three minute time limit. Speakers may be asked questions by the Members of the Committee, but are not permitted to ask questions of others or to join in the debate. Speakers are not permitted to circulate or display plans, photographs, illustrations or textual material during the Committee meeting as any such material should be sent to the Members *and* officers in advance of the meeting to allow them time to consider the content.

Content of Officer's Report

It should be noted that the Officer's report will endeavour to include a summary of the relevant site characteristics, site history, policy issues, consultations carried out with both internal and external consultees and the public and then seek to make a professional judgement as to whether permission should be granted. However, the officer's report will usually summarise many of the issues, particularly consultations received from consultees and the public, and anyone wishing to see the full response must ask to consult the application file.

Status of Officer's Recommendations and Committee's Decisions

The recommendations contained in this report are made by the officers at the time the report was prepared. A different recommendation may be made at the meeting should circumstances change and the officer's recommendations may not be accepted by the Committee.

In order to facilitate debate in relation to an application, the Chairman will move the officer's recommendations in the report, which will be seconded by the Vice Chairman. Motions are debated by the Committee in accordance with the Council's Rules of Procedure. A binding decision is made only when the Committee has formally considered and voted in favour of a motion in relation to the application and, pursuant to that resolution, the decision notice has subsequently been issued by the Council.

Conditions and Reasons for Refusal

Suggested reasons for refusal and any conditions are set out in full in the officer's recommendation.

Officers or the Committee may add further reasons for refusal or conditions during the Committee meeting and Members may choose to refuse an application recommended for permission by the Officers or to permit an application recommended for refusal. In all cases, clear reasons will be given, by whoever is promoting the new condition or reason for refusal, to explain why the change is being made.

Decisions Subject to Completion of a Planning Obligation

For some applications, a resolution is passed to grant planning permission subject to the completion of an appropriate planning obligation (often referred to as a Section 106 agreement). The obligation can restrict development or the use of the land, require operations or activities to be carried out, require the land to be used in a specified way or require payments to be made to the authority.

New developments will usually be required to contribute towards the infrastructure required to serve a site and to cater for additional demand created by any new development and its future occupants. Typically, such requirements include contributions to community facilities, village halls, parks and play areas, playing fields and improvements to roads, footpaths, cycleways and public transport.

Upon completion of the obligation, the Head of Planning and Building is delegated to grant permission subject to the listed conditions. However, it should be noted that the obligation usually has to be completed sufficiently in advance of the planning application determination date to allow the application to be issued. If this does not happen, the application may be refused for not resolving the issues required within the timescale set to deal with the application.

Deferred Applications

Applications may not be decided at the meeting for a number of reasons as follows:

- * The applicant may choose to withdraw the application. No further action would be taken on that proposal and the file is closed.
- * Officers may recommend deferral because the information requested or amended plans have not been provided or there has been insufficient time for consultation on amendments.
- * The Committee may resolve to seek additional information or amendments.
- * The Committee may resolve to visit the site to assess the effect of the proposal on matters that are not clear from the plans or from the report. These site visits are not public meetings.

Visual Display of Plans and Photographs

Plans are included in the officers' reports in order to identify the site and its surroundings. The location plan will normally be the most up-to-date available from Ordnance Survey and to scale. The other plans are not a complete copy of the application plans and may not be to scale, particularly when they have been reduced from large size paper plans. If further information is needed or these plans are unclear please refer to the submitted application in the reception areas in Beech Hurst, Andover or the Former Magistrates Court office, Romsey. Plans displayed at the meeting to assist the Members may include material additional to the written reports.

Photographs are used to illustrate particular points on most of the items and the officers usually take these. Photographs submitted in advance by applicants or objectors may be used at the discretion of the officers.

Human Rights

"The European Convention on Human Rights" ("ECHR") was brought into English Law, via the Human Rights Act 1998 ("HRA"), as from October 2000.

The HRA introduces an obligation on the Council to act consistently with the ECHR.

There are 2 Convention Rights likely to be most relevant to Planning Decisions:

- * Article 1 of the 1st Protocol - The Right to the Enjoyment of Property.
- * Article 8 - Right for Respect for Home, Privacy and Family Life.

It is important to note that these types of right are not unlimited - although in accordance with the EU concept of "proportionality", any interference with these rights must be sanctioned by Law (e.g. by the Town & Country Planning Acts) and must go no further than necessary.

Essentially, private interests must be weighed against the wider public interest and against competing private interests. Such a balancing exercise is already implicit in the decision-making processes of the Committee. However, members must specifically bear Human Rights issues in mind when reaching decisions on all planning applications and enforcement action.

Natural Environment and Rural Communities Act 2006 (NERC)

The Council has a duty under the Natural Environment and Rural Communities Act 2006 as follows: *"every public authority must, in exercising its functions, have regard, so far as is consistent with the proper exercise of those functions, to the purpose of conserving biodiversity"*.

It is considered that this duty has been properly addressed within the process leading up to the formulation of the policies in the Revised Local Plan. Further regard is had in relation to specific planning applications through completion of the biodiversity checklists for validation, scoping and/or submission of Environmental Statements and any statutory consultations with relevant conservation bodies on biodiversity aspects of the proposals.

Provided any recommendations arising from these processes are conditioned as part of any grant of planning permission (or included in reasons for refusal of any planning application) then the duty to ensure that biodiversity interest has been conserved, as far as practically possible, will be considered to have been met.

Other Legislation

Section 38(6) of the Planning and Compulsory Purchase Act 2004 requires that determination of applications be made in accordance with the Development Plan unless material considerations indicate otherwise. The Development Plan for the Borough comprises the Test Valley Borough Revised Local Plan (2016). Material considerations are defined by Case Law and includes, amongst other things, draft Development Plan Documents (DPD), Supplementary Planning Documents (SPD) and other relevant guidance including Development Briefs, Government advice, amenity considerations, crime and community safety, traffic generation and safety.

On the 24 July 2018 the Government published a revised National Planning Policy Framework (NPPF). The revised NPPF replaced and superseded the previous NPPF published in 2012. The revised NPPF is a material consideration in planning decisions.

So that sustainable development is pursued in a positive way, at the heart of the revised NPPF is a presumption in favour of sustainable development. Decisions should apply a presumption in favour of sustainable development. This does not change the statutory status of the development plan as a starting point for decision making. Planning law requires that applications for planning permission must be determined in accordance with the development plan unless material considerations indicate otherwise. Where a planning application conflicts with an up to date development plan, permission should not usually be granted. Local planning authorities may take decisions which depart from an up to date development plan, but only if material considerations in a particular case indicate that the plan should not be followed.

For decision-taking, applying the presumption in favour of sustainable development means:

- Approving development proposals that accord with an up to date development plan without delay; or
- Where there are no relevant development plan policies, or the policies which are most important for determining the application are out of date, granting permission unless:
 - The application of policies in the revised NPPF that protect areas or assets of particular importance provides a clear reason for refusing the development proposed; or

- Any adverse impact of doing so would significantly and demonstrably outweigh the benefits, when assessed against the policies in the revised NPPF when taken as a whole.

Existing Local Plan policies should not be considered out of date because they were adopted prior to the publication of the revised NPPF. Due weight should be given to them, according to their degree of consistency with the revised NPPF (the closer the policies in the Local Plan to the policies in the revised NPPF, the greater the weight that may be given).

ITEM 7

APPLICATION NO.	18/01953/FULLS
APPLICATION TYPE	FULL APPLICATION - SOUTH
REGISTERED	24.07.2018
APPLICANT	Mr and Mrs L. Ashford
SITE	Land adjacent to Meadow View, Houghton, Stockbridge, SO20 6LT, HOUGHTON
PROPOSAL	Erection of a detached dwelling
AMENDMENTS	Landscape Visual Impact Assessment 16.10 2018; Tree Canopy Projection Plan 23.10.2018.
CASE OFFICER	Ms Astrid Lynn

Background paper (Local Government Act 1972 Section 100D)

1.0 INTRODUCTION

- 1.1 This application is referred to Planning Control Committee (PCC) because the Southern Area Planning Committee (SAPC) was minded to refuse planning permission for reasons that the Head of Planning and Building advised could not be substantiated. In all cases a decision would result in a risk of costs being awarded against the Council at appeal.
- 1.2 A copy of the Officer's report to the 9 October 2018 SAPC and its associated update paper are attached as **Appendix A** and **Appendix B** respectively.

2.0 PLANNING CONSIDERATIONS

- 2.1 Members of SAPC resolved to refuse planning permission contrary to the Officer recommendation. Members considered that the proposed development would represent an unacceptable size; loss of woodland subject to a TPO; would reduce distinctive village features that would be unacceptable and detrimental to the character and setting of the Conservation Area; and would result in the irresistible urge to fell trees to protect future living conditions, adversely affecting the character and appearance of the area.
- 2.2 **Reason for refusal 1: Impact on the character and appearance of the area.**
The reason for refusal by the SAPC referenced conflict with Policy E1 which requires that development "*should integrate, respect and compliment the character of the area in which the development is located in terms of layout, appearance, scale, materials and building styles*", and:
(d) *that developments "makes efficient use of the land whilst respecting the character of the surrounding area and neighbouring uses"*.
Policy E2 requires that development "*does not have a detrimental impact on the appearance of the immediate area and the landscape character of the area within which it is located.*"

- 2.3 Members of SAPC referenced the bulk of the dwelling failing to reflect the character and appearance of the area in terms of policies E1 and E2. The discussions about harm centred on views of the site from the main village street – this public vantage point also forms part of the route of the Clarendon Way.
- 2.4 As is described in the officer's recommendation, the area is characterised by dwellings of a similar scale and ridge height. The proposal represents a detached dwelling comparable to those in the vicinity, perpendicular to the road and contained within existing woodland and additional planting. The design is considered to be one that gives the appearance of evolving over time, breaking up the overall massing of the building, providing for the long term maintenance of the plot in woodland management. Proposed materials of clay tiles and brick are considered appropriate local materials sympathetic to the settlement.
- 2.5 The discussion at SAPC focussed on the impact the development would have from the Village Street and the related impact on the character and appearance of the area. Officer's advice is that the additional proposed hedgerow planting would limit this impact to the driveway only, in character with other dwellings of the village within the settlement and Conservation Area. Additional supporting information submitted on 16 October 2018 following the SAPC meeting, the LVIA clarifies this point indicating that the proposed dwelling with associated additional planting, would only be visible from the driveway, with the additional benefit of new managed planting to enhance existing hedgerow and tree cover on site over the next 20 years.
- 2.6 The 0.74acre site is considered a spacious setting for a single detached dwelling within a settlement, respecting the character of the surrounding area and neighbouring uses. The development for one dwelling is therefore considered compliant with policies E1 and E2 and guidance contained within the NPPF.
- 2.7 **Reason for refusal 2: Loss of woodland adversely affecting the character of the area.**
Members of SAPC raised concerns that the development would result in woodland subject to a Tree Preservation Order, being directly lost and therefore adversely affecting the character and appearance of the area.
- 2.8 As described in the officer's report, the Tree Preservation Order is not affected by this development, and would remain in place. The site provides a green wooded area visible from some distance on the Clarendon Way and from the Sheepbridge. Its presence therefore offers a significant landscape contribution to the setting and appearance of the settlement from both long distance and short distance views.
- 2.9 Members of SAPC were advised that the development proposal included an Arboricultural Impact Assessment and Tree Protection Plan that concluded that the proposed changes will affect trees, but that subject to appropriate protection, the development will have no adverse impact on the contribution the woodland makes to the character and appearance of the wider area.

Indeed, with the proposed planting and a 20 year management scheme proposed (secure via condition) the scheme would result in an enhancement to the area on the medium to long term. in accordance with policy E2.

- 2.10 The submission is now additionally supported by a document depicting the existing and potential 'Tree Canopy Spread' with and without the development. The TVBC Tree Officer notes that this document explains that although the site is protected by a Tree Preservation Order, the Local Planning Authority has little control over the future management of the Copse without this development. This explains that apparent failure of the woodland as depicted in the Canopy spread plan that has been produced since SAPC by the applicant. The plan also identifies that Ash-die back will also contribute to the loss of woodland in the foreseeable future. In addition, this supporting document clarifies that the proposed development enables the site to increase and improve trees on site, however, without it, there is no power to enforce replacement of trees lost naturally, leaving trees to collapse, and scrub, laurel and brambles to inhabit the woodland floor, which in turn would restrict the natural regeneration of new trees.
- 2.11 The officer notes that without this development, the TPO woodland would degenerate within 20 years, without controls, to the detriment of the character of the area, and this position is considered to weigh significantly in favour of the development. The proposal, it is considered provides an opportunity to reflect the strong feeling locally of the visual value of woodland on this site.
- 2.12 **Reason for refusal 3: Impact on the Conservation Area**
Members expressed their concern that the development would remove roadside hedgerow which provides characteristic roadside boundary treatment, which is considered characteristic of the character and setting of the Conservation Area. They felt that the inclusion of a new dwelling with driveway accessed from the Village Street, would be detrimental to the character and setting of the Conservation Area.
- 2.13 The Officer's report notes that the proposal would reinstate the boundary hedgerow, and would also retain the southern part of the site as managed woodland. The SAPC report notes that the Tree, Landscape and Conservation and Design Officer's raise no objection to the proposal. The SAPC report clarifies that the on-site mature trees, planned retention and supplemental planting would in combination provide no views through the site to the River Test and the Sheepbridge. Indeed the SAPC report states that the development would result in a neutral impact on the setting and appearance of the Conservation Area.
- 2.14 In reaching their decision at SAPC, Councillors did clarify further how the new dwelling and driveway would be detrimental to the character and setting of the Conservation Area, in contradiction to the advice provided in the Officer's report. Consequently members were advised that this refusal reason would therefore carry a risk that costs could be awarded against the Council in any subsequent appeal

2.15 **Reason for refusal 4: Threat to fell trees subject to TPO's.**

Members expressed their concern that the development would as a consequence of the proximity of the dwelling and its private amenity space to woodland, result in the irresistible urge to fell trees to protect future living conditions. The threat to fell would result in the loss of trees and the woodland area that makes a positive contribution to the character and appearance of the area.

2.16 The Officer's report to SAPC explains that 14 trees are shown for removal, including Grade B and C, however, 16 trees are shown for planting. all standard trees, providing immediate tree cover. In addition, the Tree Officer states no objection to the proposal.

2.17 To assist members in understanding the all officer advice in this respect, an LVIA and a Tree Canopy Report are now submitted, in support of the development. These are considered to clarify that the Copse would not be detrimentally impacted by the development and, further, that the development enables the long term management and retention of the TPO woodland, which cannot be otherwise ensured.

2.18 In reaching this resolution at SAPC, Councillors did not explicitly set out their concerns. In addition Officers are of the opinion that the scheme is acceptable in this respect

2.19 **Other matters**

Much of the SAPC discussions focussed on the differences between the previously refused scheme and that now proposed. Officers provided plans in the agenda papers of both the layout and elevations of both schemes, and these remain available in Appendix A.

2.20 Officers advised SAPC that the scheme had significantly changed in the intervening period with regard to the size, design and massing of the proposed dwelling, clarification over any retained trees, improvements to the boundary hedgerows (new) and the provision of significant amounts (and size) of new replacement tree planting that is now included. In addition to this the current scheme. As mentioned elsewhere in this report, the applicant has also committed to a 20 year management and maintenance scheme for the woodland that would remain post-construction. It is considered that these changes represent significant alterations to the previously refused scheme that the scheme is now acceptable.

3.0 **CONCLUSIONS**

3.1 It remains the consideration of the Head of Planning and Building that the proposal, subject to the required conditions would have no significant adverse impact on the character and appearance of the area when viewed from the village Street or the Clarendon Way or from the Sheepbridge, neither would it significantly or unacceptably impact upon the woodland subject to a woodland TPO, the Conservation Area or the landscape. There is significant scope to retain and enhance the woodland presence on the site post-construction of the new dwelling and thereby preserve the character and appearance of the Conservation Area. It is also material to consider the effect of the 'do nothing'

approach and how such an approach might have on future tree cover at the site. The applicant has provided further information to demonstrate how the scheme would assist in delivering the community aspirations for a woodland to make a positive contribution to the street scene, and setting of Houghton.

4.0 RECOMMENDATION OF THE SOUTHERN AREA PLANNING COMMITTEE TO PLANNING CONTROL COMMITTEE

REFUSE for the reasons:

- 1. The proposed bulk of the dwelling is not acceptable in that its size would fail to reflect the character and appearance of the area and therefore not accord with Policies E1 and E2 of the Test Valley Borough Revised Local Plan (2016)**
- 2. The proposed dwelling will result in the loss of woodland which is the subject of a Tree Preservation Order. The loss of the woodland would adversely affect the character and appearance of the area, contrary to Policies E1 and E2 of the Test Valley Borough Revised Local Plan (2016).**
- 3. The Bossington and Houghton Conservation Area is characterised by linking roadside hedgerows, such as that providing the roadside boundary for this application site, by this woodland, subject of a Woodland Preservation Order and by a number of roadside Listed Buildings, which retain local design pre-eminence in the street scene. The reduction of these distinctive village features arising from this proposed development is considered unacceptable and detrimental to the character and setting of the Conservation Area, a heritage asset and contrary to Test Valley Borough Revised Local Plan (2016) policies COM2 and E9.**
- 4. The proposal would, as a consequence of the proximity of the dwelling and it's private amenity space to woodland, result in the irresistible urge to fell trees to protect future living conditions. The threat to fell would result in the loss of trees and the woodland area that makes a positive contribution to the character and appearance of the area. The proposal is contrary to Policy E2 of the Test valley Borough Revised Local Plan (2016).**

5.0 RECOMMENDATION OF THE HEAD OF PLANNING AND BUILDING PERMISSION subject to:

- 1. The development hereby permitted shall be begun within three years from the date of this permission.
Reason: To comply with the provision of Section 91 of the Town and Country Planning Act 1990 as amended by Section 51 of the Planning and Compulsory Purchase Act 2004.**
- 2. The development hereby permitted shall not be carried out except in complete accordance with the details shown on the submitted plans, numbers: 16/291/02 Rev. G; 16/291/03 Rev. H; 17347-BT7.
Reason: For the avoidance of doubt and in the interests of proper planning.**

- 3. No development shall take place above DPC level of the development hereby permitted until samples and details of the materials to be used in the construction of all external surfaces hereby permitted have been submitted to and approved in writing by the Local Planning Authority. Development shall be carried out in accordance with the approved details.**
Reason: To ensure the development has a satisfactory external appearance in the interest of visual amenities in accordance with Test Valley Borough Revised Local Plan (2016) Policy E1.
- 4. No development shall take place above DPC level of the development hereby permitted until Woodland Management Plan, and a schedule of implementation and maintenance for a minimum period of 20 years has been submitted to and approved in writing by the Local Planning Authority. The schedule shall include details of the arrangements for the phasing of the implementation and ongoing maintenance during that period in accordance with appropriate British Standards or other recognised codes of practise. Development shall be carried out in accordance with the approved schedule.**
Reason: To ensure the provision, retention and maintenance to a suitable standard of approved woodland to maintain and enhance the appearance of the site and enhance the character of the development in the interest of visual amenity and to contribute to the character of the local area in accordance with Test Valley Borough Revised Local Plan (2016) Policy E2.
- 5. Before the development hereby permitted is commenced details, including plans and cross sections, shall be submitted to and approved by the Local Planning Authority of the existing and proposed ground levels of the development and the boundaries of the site and the height of the ground floor slab and damp proof course in relation thereto. Development shall be undertaken in accordance with the approved details.**
Reason: To ensure satisfactory relationship between the new development and the adjacent buildings, amenity areas and trees in accordance with Test Valley Borough Revised Local Plan (2016) Policies E1 and E9.
- 6. The development hereby approved shall be designed and built to meet Regulation 36 2 (b) requirement of 110 litres/person/day water efficiency set out in part G2 of Building Regulations 2015.**
Reason: In the interests of improving water usage efficiency in accordance with policy E7 of the Test Valley Borough Revised Local Plan 2016.
- 7. At least the first 6 metres of the access track measured from the nearside edge of carriageway of the adjacent highway shall be surfaced in a non-migratory material prior to the use of the access commencing and retained as such at all times.**
Reason: In the interest of highway safety in accordance with Test Valley Borough Revised Local Plan (2016) Policy T1
- 8. Any gates shall be set back at least 6 metres from the edge of the carriageway of the adjoining highway and the access shall be splayed at an angle of 45 degrees from this point to the edge of the highway.**

- Reason: In the interest of highway safety in accordance with Test Valley Borough Revised Local Plan (2016) Policy T1**
9. **Prior to the commencement of the use or first occupation of the building hereby permitted, the car parking space(s), turning and manoeuvring area shall be constructed, surfaced and laid out in accordance with the approved plans. The area of land so provided shall be maintained at all times for this purpose.**
- Reason: To ensure sufficient off-street parking has been provided and in the interest of highways safety in accordance with the Test Valley Revised Local Plan 2016 Policies T1 and T2.**
10. **Prior to the commencement of development full details of the layout for the parking and manoeuvring on site of contractor's and delivery vehicles during the construction period shall be submitted to and approved in writing by the Local Planning Authority. The approved scheme shall be implemented prior to the commencement of development and retained for the duration of the construction period.**
- Reason: In the interest of highway safety and in the interest of protecting Trees subject to a Woodland Preservation Order in accordance with Test Valley Borough Revised Local Plan (2016) Policies T1 and E2.**
11. **Prior to the commencement of development the visibility splays, reference Plan 16/291/03 Rev. H shall be provided. Nothing within the approved visibility splays shall exceed 1 metre above the level of the adjacent carriageway (including the land level and any walls, fences and vegetation). Notwithstanding the provisions of the Town and Country Planning (General Permitted Development) Order 2015 (or any Order revoking and re-enacting that Order) these visibility splays shall be maintained in accordance with the above details at all times.**
- Reason: In the interest of highway safety in accordance with Test Valley Borough Revised Local Plan (2016) Policy T1**
12. **Development shall proceed in accordance with the measures set out in section 6.1 'Mitigation' of the Ecological Assessment- Interim Report Land at Meadow View, Houghton' (Aluco Ecology, June 2018).**
- Reason: To avoid impacts to protected and notable species and to conserve and enhance biodiversity in accordance with Policy E5 of the Test Valley Revised Local Plan DPD.**
13. **All works to existing trees, together with the provision of new tree planting, and new boundary hedging (including the new hedge along the road frontage of the dwelling) shall be carried out in accordance with the details contained in Drw.No.17347-BT7 (Barrell Tree Consulting) prior to first occupation of the dwelling hereby permitted.**
- Reason: To ensure that only appropriate works to the trees identified on this plan are undertaken, and that suitable planting takes place on-site in a timely manner, to ensure an appropriate tree cover remains following construction of the new dwelling, to protect the character and appearance of the Conservation Area in accordance with Policy E9 of the Test Valley Borough revised Local plan (2016).**

- 14. Prior to development taking place tree protective fencing shall be erected in accordance with the details contained in Drw.No.17347-BT7 (Barrell Tree Consulting), the "Arboricultural Assessment and Method Statement" (Ref: 17347-AA6-PB), and the report "Manual for Managing Trees on development sites" (Barrell Tree Consulting). The tree protective measures shall be retained on site for the full duration of the construction activity.**

Reason: To ensure that suitable tree protection has been erected prior to work being undertaken on site to minimise the chance of accidental damage to trees, and that appropriate tree cover remains following construction of the new dwelling, to protect the character and appearance of the Conservation Area in accordance with Policy E9 of the Test Valley Borough revised Local plan (2016).
- 15. Notwithstanding the provisions of the Town and Country Planning (General Permitted Development) Order 2015 (or any order revoking and re-enacting that Order with or without modification), no garages or additional outbuildings shall be erected other than those expressly authorised by this permission.**

Reason: In order that the Local Planning Authority can exercise control in the locality in the interest of the local amenities in accordance with Test Valley Borough Revised Local Plan (2016) Policy E2.

Notes to applicant:

- 1. In reaching this decision Test Valley Borough Council (TVBC) has had regard to the National Planning Policy Framework and takes a positive and proactive approach to development proposals focused on solutions. TVBC work with applicants and their agents in a positive and proactive manner offering a pre-application advice service and updating applicants/agents of issues that may arise in dealing with the application and where possible suggesting solutions.**
- 2. Birds' nests, when occupied or being built, and the widespread species of reptile receive legal protection under the Wildlife and Countryside Act 1981 (as amended). It is highly advisable to undertake clearance of potential bird nesting habitat (such as hedges, scrub, trees, suitable outbuildings etc.) outside the bird nesting season, which is generally seen as extending from March to the end of August, although may extend longer depending on local conditions. If there is absolutely no alternative to doing the work in during this period then a thorough, careful and quiet examination of the affected area must be carried out before clearance starts. If occupied nests are present then work must stop in that area, a suitable (approximately 5m) stand-off maintained, and clearance can only recommence once the nest becomes unoccupied of its own accord. Reptile habitat such as compost heaps should be carefully cleared by hand during warmer months as if hibernating reptiles are disturbed they will die. Any reptiles revealed should be moved to adjacent retained rougher / boundary habitat or allowed to move off of their own accord.**

- 3. Bats and their roosts receive strict legal protection under the Wildlife and Countryside Act 1981 (as amended) and the Conservation of Habitats and Species Regulations 2017. All work must stop immediately if bats, or evidence of bat presence (e.g. droppings, bat carcasses or insect remains), are encountered at any point during this development. Should this occur, further advice should be sought from Natural England and/or a professional ecologist.**
 - 4. The various trees standing within this site are all protected by virtue of standing within the Houghton Conservation Area and also by Tree Preservation Order (TPO.TVBC.1124) Damage to any of the trees not identified for removal on the approved plans is an offence. Failure to comply in full with Barrell Tree Consultancy Arboricultural Assessment and Method Statement 17347-AA2-PB is likely to result in damage to the trees. Damage to the trees may lead to the prosecution of those undertaking the work and also of those instructing, causing or permitting the works.**
-

APPENDIX A

Officer Report to Southern Area Planning Committee on 9 October 2018

APPLICATION NO.	18/01953/FULLS
APPLICATION TYPE	FULL APPLICATION - SOUTH
REGISTERED	24.07.2018
APPLICANT	Mr and Mrs L. Ashford
SITE	Land adjacent to Meadow View, Houghton, Stockbridge, SO20 6LT, HOUGHTON
PROPOSAL	Erection of a detached dwelling
AMENDMENTS	Shade and sunlight study; Ecology Survey. 02/08/2018. Exterior materials: Brick. 24/08/2018. Elevations amended 28.08.2018.
CASE OFFICER	Ms Astrid Lynn

Background paper (Local Government Act 1972 Section 100D)

1.0 INTRODUCTION

- 1.1 The application is presented to Southern Area Planning Committee at the request of a Member for the reason:

“due to the public perception that it is against the security of the copse on which a preservation order (or equivalent) was served”.

2.0 SITE LOCATION AND DESCRIPTION

- 2.1 The application is made in full on a 0.74 acre site located within the settlement of Houghton, within the Conservation Area. The site is south of Houghton Road, between the dwellings known as Mayfield House and Dianthus. Meadow View and South End Cottages are opposite the site, to the north of Houghton Road. Garden and pasture land outside the settlement lies, to the south east of the site. Beyond this is the River Test, a Site of Special Scientific Interest (SSSI). The route of the Clarendon Way, a Public Right of Way, passes the site to the north, along Village Road.
- 2.2 The site is the subject of a Woodland Tree Preservation Order, and contains trees and bushes. A single range of derelict pigsties and outbuildings are sited within this undergrowth, in the north of the site, with gable end to the road side, and a further small former building is indicated in the central area of the site.
- #### **3.0 PROPOSAL**
- 3.1 The proposal is to construct a single detached dwelling. Indicative details for a package treatment plant, new access and entrance gates are included in the submission. The proposed dwelling is located in the northern end of the application site, in a main and smaller section connected by a glass link. The proposed dwelling would therefore have a number of roof levels and gables, and two chimneys. The proposed roofing material is handmade clay tiles.

Exterior walls would be in hand made brick with a plinth in blue engineering bricks. The glazed link would also be erected on a plinth of blue engineering bricks.

- 3.2 The ground floor would comprise living rooms across the entire width of the main house. The first floor would comprise four en-suite bedrooms, and a dressing room for the master bedroom.
- 3.3 Plans depict a vehicular access opposite Meadow View, with entrance gates set back 6m from the road side. An on-site turning head and three parking spaces are proposed to the north of the proposed dwelling.
- 3.4 The roofline and footprint is varied, considered to represent a building which has grown organically over time.
- 3.5 Details for a Klargestor sewage treatment tank are submitted, indicating their location in the driveway to the north of the proposed dwelling, 5m from the boundary with the garden to Mayfield.

4.0 **HISTORY**

- 4.1 17/02017/FULLS Demolition of existing buildings on site and construction of detached dwelling to include package treatment plant, new access and entrance gates. Refused 02.11.2017.
 - 1. The proposed single dwelling is a bulky single mass, considered intrusive and uncharacteristic, not well integrated into the area character, or the site which is subject to a Woodland Tree Preservation Order, detrimental to this woodland and the surrounding Conservation Area. The proposed dwelling house is considered bulky and unacceptably intrusive contrary to Test Valley Borough Revised Local Plan policies COM2 and E1.
 - 2. The site provides a green wooded area; subject to Woodland Tree Preservation Order, with mature trees visible from the Clarendon Way and from the Sheepsbridge, which crosses the River Test to the north of the site. It provides a verdant hedgerow alongside the Village street, characteristic of the Conservation area. The loss of a large part of this woodland and road side hedgerow is considered detrimental to the landscape character of the immediate area, contrary to Test Valley Borough Revised Local Plan policies COM2 and E2.
 - 3. Inadequate survey and mitigation information has been submitted in order for the local planning authority to conclude that the proposed development would not have an adverse impact on protected species. The proposed development is therefore considered contrary to policies COM2 and E5 of the Test Valley Borough Revised Local Plan (2016) and the Conservation of Habitats and Species Regulations.

4. The Bossington and Houghton Conservation Area is characterised by linking roadside hedgerows, such as that providing the roadside boundary for this application site, by this woodland, subject of a Woodland Preservation Order and by a number of roadside Listed Buildings, which retain local design pre-eminence in the street scene. The reduction of these distinctive village features arising from this proposed development is considered unacceptable and detrimental to the character and setting of the Conservation Area, a heritage asset and contrary to Test Valley Borough Revised Local Plan (2016) policies COM2 and E9.
5. Inadequate survey and mitigation information has been submitted in order for the local planning authority to conclude that the proposed development would not have an adverse impact on the amenity of future occupants of the proposed development, arising from potential overshadowing from the surrounding woodland. The proposed development is therefore considered contrary to policies COM2 and LHW4 of the Test Valley Borough Revised Local Plan (2016).
6. The eastward gable end windows for the development subject to this application are within 5m of the rear garden for Mayfield. Loss of privacy arising from this overlooking is considered detrimental to the amenity of Mayfield and its occupants, and contrary to Test Valley Borough Revised Local Plan (2016) policies COM2 and LHW4.

Plans associated with this refused application are included in the agenda paper as **Appendix A**.

- 4.2 17/01485/TREES Proposal works to trees as per schedule received. Objection. Woodland TPO. 10.10.2017.
- 4.3 17/02242/TPOS Carry out various tree works as described in survey schedule submitted with application. Part Consent, part refusal. 17.10.2017.
- 4.4 TPO.TVBC.1124 Trees within the boundaries of the woodland area opposite Meadow View and adjacent to Mayfield House, Houghton. 12.10.2017.
- 5.0 **CONSULTATIONS**
- 5.1 **Policy Officer** – No objection.
- 5.2 **Landscape Officer** – No objection subject to conditions concerning planting details, including implementation and subsequent management, and delivering on the front boundary hedge.
- 5.3 **Conservation and Design Officer** – No objection subject to conditions.
- 5.4 **Tree Officer** – No objections subject to conditions.
- 5.5 **HCC Ecologist** – No objection subject to a condition and notes.
- 5.6 **Highways Engineer** – No objection subject to conditions.

6.0 **REPRESENTATIONS Expired 24.08.2018**

6.1 **Houghton Parish Council – Objection** (Summarised):

- No housing need for large dwellings. Test Valley has sufficient housing Land Supply. (HLS);
- Village Design Statement and Neighbourhood Plan. (Not yet published).
- Seeks to protect the last green spaces in the village.
- Houghton and Bossington Conservation Document.
- The copse contains 'important trees and groups of trees'. It characterises the village as having distinctive features of interlinking hedgerows and listed buildings close by. The reduction of this distinctive village feature is unacceptable and detrimental to the character and setting of the Conservation Area, contrary to policies COM2 and E9.
- Woodland Preservation Order. This application would involve cutting down valuable trees, losing habitat for the village rookery and impacting on the biodiversity of the wood, thus contravening policy COM2 and E5.
- This development is on the site of the last woodland copse in the village.
- Landscape impact. The development would be visible from Sheepbridge and also lies adjacent to the Clarendon Way. Both are visited regularly by tourists and locals, who appreciate the area and the birdlife and wildlife.
- Development. There have already been significant developments approved by TVBC very close to the site. The area will have changed beyond recognition if the woodland were to be developed with the further loss of green and wildlife abundant spaces.
- Planning History. The Parish Council would like to draw attention to the notice of refusal for 17/02017/FULLS. The reasons for refusal are still applicable to this application.
- Houghton Parish Council objects to this proposal. It contravenes 6 policies of the Revised Local Plan.

6.2 **Forty letters of objection** have been received from occupants of properties in the village. These objections include:

6.3 Same refusal reasons as the 2017 refused case

The reasons for refusal last year are still overwhelmingly relevant and the application should be refused again;

6.4 Out of character with landscape of the village

- This development would have a negative impact on the character of this area of the village;
- A large dwelling in an acknowledged woodland;
- It will be totally out of sympathy with the character of the village;
- The Test Valley generally is a highly manicured area – any small pieces of land which are relatively unspoilt (some would say unkempt) are to be highly valued and protected;
- Villagers do not wish to be living in a suburban style community where all the green spaces and woodland have been built over loss of characteristic roadside hedgerow;

6.5 Biodiversity impact

- Local residents would like to see the site remain a small wooded area;
- It would be a disaster if the wooded copse and wildlife were destroyed for yet another un needed large property;
- It is unacceptable for a building to be constructed on a green wooded area which contributes an important habitat for local wildlife and a key feature of the conservation area;
- A significant number of trees and other natural environment has been lost to other building works or still planned for this side of Houghton. This copse must be maintained to preserve the habitat and retain some semblance of the rural character of this part of the village;
- The area is so close to the river and it will have its own biological microcosm that should be protected;
- Would seriously affect the bio diversity of the wood which is presently home to the village rookery, has owls and bats in it as well as slow worms, all protected species:
- Loss of valuable green lung & habitat; loss of habitat for protected species;
- Loss of a significant and rare copse;
- Concerns expressed for the wellbeing of the Rookery and for bats in particular as well as owls and other protected species;
- How can you say that this application will protect or add to, bio-diversity and heritage?

6.6 Loss of defining characteristic of green spaces between properties

- Loss of a green space and interlinking hedgerow between listed buildings;
- Loss of a valuable green lung within the village;

6.7 Impact on views from PROW

- Impacts on views from the Clarendon Way and Sheepsbridge, which are Public Rights of Way;

6.8 No housing need

- For a further luxury home in the village;
- Need for small affordable dwellings;
- TVBC has publicly states that it has sufficient land for housebuilding for the next 15 years
- There may be good reasons for social or affordable housing, but the current proposal appears to contribute absolutely nothing to the wellbeing of the village.

6.9 Over development

- There is enough development in this end of the village;
- The village has had 28 new houses permitted in the last 3 years, half very close to the site;
- The large proposed dwelling is out of context;
- There are 3 derelict dwellings opposite the site – evidencing no need for this property’;
- In recent years the village has had its fair share of large properties being built and the rural village, country soul of Houghton is disappearing.

- The village has seen an approximate 18 -20% increase in houses in the past 5 years which has massively diminished the rural nature of the village;
- Uncharacteristic and not well integrated design.

6.10 Highways impact

- Traffic generation, parking and safety.

6.11 Lack of amenities for new development

- Lack of light and sunlight - Little natural light arising from building a dwelling within a woodland, with related threat to fell trees subject to TPOs;
- The proposed property, whilst slightly smaller than the previous proposal, would still require the felling of a significant number of mature trees, and would inevitably lead to a gradual clearance of the whole site;
- The village lacks services for more development – doctors; public transport, internet, electricity outages every winter.

6.12 Drainage matters

Normal site conditions are boggy and it will probably be necessary to pile drive the plot to construct footings, with related impacts on the root systems of trees.

6.13 Loss of Woodland subject to a Woodland TPO

- Would like someone to buy this and keep it maintained as a much needed wooded area this end of the village;
- Threat to fell arising from development in close proximity to mature trees;
- Miss Beales Copse was never residential, it has disused Pigsties on site and has been a woodland for 30 years;
- Loss of a unique small woodland;.
- This particular instance will destroy the last piece of woodland in the village;
- It would involve cutting down a large amount of trees in the middle of the wood and would change the appearance of the wood and the conservation area forever contrary to policies COM2 and E1;
- It would be contrary to the Woodland Preservation Order to cut down mature trees that are visible from the Clarendon Way and Sheepbridge, changing the street scene and conservation area with changes to trees and hedges along the road;
- Little natural light arising from building a dwelling within a woodland, with related threat to fell trees subject to TPOs;
- The proposed property, whilst slightly smaller than the previous proposal, would still require the felling of a significant number of mature trees, and would inevitably lead to a gradual clearance of the whole site;

6.14 Design and the Village Design Statement (lodged with the TVBC)

- States that the land is a significant and rare copse which strongly reinforces the rural character of the village road;
- Building on this land would destroy beyond recognition the last woodland copse in the village.
- The reference to 19-22 south End Cottages, refers to cottages built in 1875 as an interpretation of the Kentish vernacular. Does copying this produce a Hampshire style?

6.15 Overlooking and loss of privacy

The positioning of the property means that the front of the house looks directly onto the front of our property with three bedroom windows facing directly into each other, and will adversely affect privacy contrary to policies COM2 and LHW4.

6.16 Impact on this part of the Conservation Area

- This part of the Conservation Area needs to retain this particular wooded area of land which has always had a lot of coppiced wood and large trees;
- the proposed building is out of character with the area;

6.17 Heritage impact - adverse Conservation Area impacts

The site was owned and used by its original owners of Meadow View as a large vegetable plot, with a pig and pig sty, chicken and a few sheep. There was a long wooded barn alongside the road associated with the livestock.

7.0 **POLICY**

7.1 Government Guidance

National Planning Policy Framework 2018(NPPF)
National Planning Practice Guidance (NPPG)

7.2 Test Valley Borough Revised Local Plan (2016)(TVBRLP)

SD1 – Presumption in favour of sustainable development
COM2 – Settlement hierarchy
COM7 – Affordable Housing
E1 – High quality development in the Borough
E2 – Protect, conserve and enhance the landscape character of the Borough
E5 – Biodiversity
E7 – Water management
E9 – Heritage
LHW4 – Amenity
T1 – Managing movement
T2 – Parking standards

7.3 Supplementary Planning Documents (SPD)

Bossington and Houghton Conservation Area 1990.

7.4 Other

Draft Houghton Neighbourhood Plan (Area designation 13.06. 2017).

8.0 **PLANNING CONSIDERATIONS**

8.1 The main planning considerations are:

- The principle of development
- Heritage impacts -Conservation Area; Listed Buildings; Archaeology
- Landscape character impact
- Biodiversity Impact
- Design
- Amenity impact
- Highways Impact: Village Road and Clarendon Way
- Drainage impact

8.2 **The principle of development**

The development is located within the settlement boundary of Houghton as set out in the Revised Borough Local Plan 2016. (TVBRLP). Policy COM2 of the TVBRLP states that the principle of development will be permitted provided that it is appropriate to other material planning considerations. Therefore in principle, the development proposal is acceptable. It is not necessary for the applicant to demonstrate, for the purpose of complying with Policy COM02 in this instance that there is a need for the dwelling (“luxury” or “affordable”). Other material considerations are now addressed.

8.3 **Heritage impacts**

Heritage impacts include impacts on the Houghton and Bossington Conservation Area, adjacent listed buildings and on archaeology. Heritage matters are addressed within TVBRLP policy E9: Heritage, which requires development proposals affecting heritage assets to make positive contributions to sustaining or enhancing the significance of the heritage asset, and requires that development proposals are informed through an assessment proportionate to its significance.

8.4 Houghton and Bossington Conservation Area is characterised by key features, including:

- A dispersed linear settlement with hedgerows linking elements between groups of dwellings.
- Important open areas to the east adjacent the River Test.
- Characteristic local estate cottages.
- Views eastwards across the valley of the River Test and from footpaths on the western village edge.

8.5 The key feature characteristic of the Conservation Area on this site is the hedgerow along the road frontage, providing a key linkage for this part of the dispersed linear settlement between Mayfield with Dianthus on the east of the Village Road and dwellings further south. The Woodland is also the remaining woodland in the village, and considered focal within the Conservation Area. The views towards this site are predominantly from the Village Street, Clarendon Way and the Sheepsbridge. It is not currently possible to view the river from within the site, due to its well vegetated Woodland nature.

8.6 The application is submitted with a current Heritage and Townscape Statement, (RMA Heritage, July 2018). This concludes that though recently designated as woodland by the Council, historic research reveals that the site was until relatively recently managed and developed at its northern end, with the site becoming overgrown in recent years. This report suggests that the proposed development would reinforce the historic linear settlement pattern of the village, and will allow the site to retain its treed character.

8.7 The proposal provides a reinstated boundary hedgerow and retains all the southern part of the woodland. The Council’s Conservation and Design Officer, the Landscape Officer, and the Tree Officer raise no objection to the proposal. Notably, due to the on-site mature trees, and planned retention, and supplemental planting, the development would not provide new views through the site to the River Test or Sheepsbridge. Conversely the public appreciation

of built development on the site when viewed from the Clarendon Way as one approaches and leaves the Sheepsbridge will also be minimised. The reduction in built form on the site (compared to the refused scheme) and the resultant dwelling appearing in the context of similarly scaled existing dwellings in this vista would, it is considered result in a more sympathetic form of development that would complement the character and appearance of the area.

8.8	Proposed development 18/01953/FULLS	Refused development 17/002017/FULLS
	11m maximum width	13m maximum width
	24m length	24m length
	No cellar	A cellar 10.5m X 9m
	Ridge height varies 7.3m, 7.8m & 8m	Ridge height 8.2m
	Single storey utility 3m from southern boundary	Two storey dwelling 3m from southern boundary
	Sewage treatment plant to the north east of the proposed dwelling	Sewage treatment plant to the south of the proposed dwelling
	Handmade brick exterior elevations	Through render exterior walls
	Blue engineering brick plinth	Natural coloured sandstone plinth

The table above clarifies the differences between the two applications on site. The reinstatement of the roadside hedgerow, the tree management proposal and the tree planting discussed in depth further below, are also considered an enhancement of the site's rural and wooded setting. In combination, these aspects are considered to result in a neutral impact on the setting of the Conservation Area, thereby preserving the character and appearance of the area. The development is considered acceptable and in accord with TVBRLP policy E9.

8.9 Listed Buildings

The application site is adjacent to a number of listed dwellings. These include Lavender Cottage, Rowans, Thatch Cottage to the south, and Houghton Farm House slightly further north, all listed Grade II and adjacent to the Village Road. Houghton Farm House is a significant former farmhouse, containing the former Village Reading Room, and is considered to have a street presence, with its large focal chimneys and concrete render exterior. The other adjacent listed buildings are well proportioned two storey dwellings, with low eaves, characteristic of estate dwellings of the village.

8.10 These properties have some prominence in the street scene, they are all visible from the Village Street, and are all characteristic of the Estate Cottages of the Conservation Area. It is considered important that they retain their prominence in this Conservation Area. The proposal is for a two storey dwelling house adjacent the Village Street. It will, by virtue of the existing, proposed planting, and the scale, massing and relative detailing that the proposal includes, will have limited visibility in the public domain. Consequently, the views to and from these Listed building from the development would, it is considered, be limited such that the setting and character of these buildings will be preserved, in accordance with policy E9 of the TVBRLP.

8.11 Archaeology

The development is located within the historic core of the village, however, the scale is considered limited in archaeological terms, and raises no archaeological issues.

8.12 **Landscape character impact/Impact on Trees**

Landscape character is addressed within TVBRLP policy E2: Protect, conserve and enhance the landscape character of the Borough. This requires development proposals to protect, conserve and enhance landscape character. An assessment of the related impact arises from the existing character, and how or if, this character is protected, conserved or enhanced.

8.13 The character of the site arises from its woodland nature and road side hedgerow which are seen in the context of the surrounding Conservation Area, with views of the site immediately adjacent from the Village Street, and more distantly, from the Clarendon Way and the Sheepsbridge. The site provides a green wooded area, designated with a Woodland Preservation Order. Mature trees on the site are visible from some distance on the Clarendon Way and from the Sheepsbridge, crossing the River Test to the north of the site, and from the road in front. The site is therefore considered of some landscape significance.

8.14 The application is supported with a Landscape and Visual appraisal Report, (WH Landscape Consultancy Ltd July 2018), which concludes that the proposed development will have no adverse effects on the key characteristics or descriptions of the site and surrounding landscape; such that the type of development proposed does not represent a key issues facing any of the relevant character types or areas. Mitigation measures proposed would integrate the proposed development into the landscape, and would also provide landscape enhancements to the sites landscape structure, in particular the boundary hedgerows and remaining woodland.

8.15 The submitted Tree Survey, Arboricultural Impact Assessment and an Arboricultural Method Statement, dated 1st September 2017, (Barrell July 2018), identify that the trees subject to removal are either of low or moderate category classification, and none form significant skyline features. The report concludes that although the proposed changes will affect trees, subject to appropriate protective measures, the development will have no adverse impact on the contribution of trees to the character in the wider setting. The Tree Officer has discussed this application at length and raises no objection.

8.16 The Tree Survey and Protection Plan submitted, provides an idea of the extent of tree work proposed. Thinning of the woodland is proposed, providing some woodland management. The trees on site have been graded A-C according to the British Standard 5837. This classification provides an indication of the quality of the trees in Arboricultural terms where Grade A represents "High Quality", Grade B "Moderate quality" and Grade C "Low quality". A number of both grade B (3no) and grade C (14no.) trees are shown for removal and a number of Grade B (3no.) and Grade C (3no.) shown for pruning. The report also indicates that it is the intention to provide a total of 16no. New heavy

standard trees. The Council's tree officer raises no objection to the way in which the trees have been classified, the extent of the tree work/removal or of the nature of the proposed planting to accompany the proposed development. It is considered that the proposed planting plan and the works proposed to the existing trees on site will enable the development to be accommodated on this site without significant detriment to the character and appearance of the area. Indeed the proposed planting will, once properly managed, help in continuing to contribute to a woodland setting to the village. The proposal is therefore considered in accord with the appearance of the immediate area and the landscape character of the area within which it is located, and in accord with TVBRLP policy E2.

8.17 Biodiversity Impact

Biodiversity impacts are addressed within TVBRLP policy E5: Biodiversity, which requires development proposals to conserve and where possible, restore and or enhance biodiversity.

8.18 The submitted report, (Aluco, July 2018), provides all ecological mitigation requirements, and matters arising can be conditioned. The application is therefore in accord with TVBRLP policy E5.

8.19 Design impact

Design is assessed within TVBRLP policy E1: High quality development in the Borough. This requires development to be of a high quality in terms of design and local distinctiveness, including integrating, respecting and complementing local area character.

8.20 Locally distinctive aspects of design include estate cottages, with relatively low eaves, varied rooflines and low ridgelines.

8.21 The proposed single dwelling appears to have a ridge height similar to those of adjacent properties, particularly Meadow View, Maybury and Southend Cottages. This can be ensured by the application of a levels condition in the recommendation. The proposed development now includes elevational treatment and detailing (see paragraph 8.8), that is considered sympathetic to the settlement.

8.22 The Village Design Statement has not been adopted, therefore the points raised by third parties in this respect, cannot be substantiated. The dwelling would appear as one that has evolved over a period of time. The main part of the dwelling runs perpendicular to the road, with a 'side extension' running parallel to it. This provides an opportunity to break the overall massing of the building up, compared to the previously refused scheme and utilising varied rooflines ensures the building's impact on its surroundings is comparable to those in the vicinity. As previously discussed, when the dwelling is seen in the context that some existing vegetation is maintained, that additional planting is proposed, and that a condition is added to ensure the long term maintenance of the plot in woodland management. The overall design of the dwelling is therefore considered well integrated into the Conservation Area character, carefully adding a well concealed but spacious dwelling within the woodland setting, and considered in accord with TVBRLP policy E1.

8.23 Amenity impact

Amenity impact is assessed within TVBRLP policy LHW4: Amenity, which assesses impact on light, sunlight, privacy and related matters. There are two elements to the consideration of these issues. Firstly, the amenity of future residents of the development and secondly, the impact of the proposal on the amenity of existing neighbouring properties.

8.24 Light and sunlight

The proposal indicates the retention of trees around the dwelling. The application is also accompanied by a Daylight and Sunlight Study, (Right of Light Consulting, July 2018). This report, partly submitted to address concerns under the previously refused planning application and the degree to which light might affect to future occupants of the property, indicates that adequate daylight and sunlight is achieved with this development proposal, in accordance with BRE standards. No detrimental associated loss of light or sunlight derives from the proposal for the neighbouring property, due to the location of the development, at this distance from Mayfield It is therefore considered that the proposal accords with TVBRLP policy LHW4: Amenity in terms of light and sunlight.

8.25 Visual impact of the Sewage treatment plant

The sewage treatment plant location would be approximately 5m from the garden to Mayfield. The siting of the sewage treatment plant would require some ground clearance and access arrangements, however, the resulting slightly raised disc at ground level within the car park and turning area, is not considered to result in an adverse impact to the amenity of either the future residents of the development or of neighbouring properties.

8.26 Privacy and overlooking

The only dwelling adjacent is Mayfield. The development would clearly introduce a new dwelling about 50m from Mayfield house itself and about 15 from the front garden of Mayfield. These distances are not considered such that any detrimental amenity impact arises from the development, to the front or side elevations of Mayfield. No windows are proposed on the boundary to the rear garden of Mayfield, and no other overlooking issues arise.

8.27 With a 50m distance between Mayfield and the proposed dwelling house, it is considered that no significant detrimental loss of privacy or overlooking arises for the occupants of the future development from occupants of Mayfield.

8.28 Highways Impact

Highways impact is assessed within TVBRLP policies T1: Managing Movement and T2: Parking Standards. These require appropriate provision of access and parking and turning areas.

8.29 The access/egress point into the site is clearly indicated on the submitted drawings. Adequate visibility splays are provided to ensure a safe means of accessing and egressing from the development. The point of access leads into an area dedicated to the parking and manoeuvring of cars. The space available can accommodate the required car parking spaces to serve the

dwelling (as per the parking standards in the TVBRLP). The proposal would not, subject to appropriate conditions, therefore give rise to acceptable solution with regard to highway safety.

8.30 Drainage impact

Drainage and water management matters are addressed in TVBRLP policy E7: Water Management. This requires development to not result in deterioration of water quality, nor to result in risk in terms of ground water quality or flooding

8.31 The submission is made with indicative details of a Sewage Treatment Plant, (STP). The siting of the STP is indicated on submitted plans, and final, technical details would be dealt with at Building Control stage.

8.32 The development is required to be designed and built to meet Regulation 36 2 (b) requirement of 110 litres/person/day water efficiency as set out in part G2 of Building Regulations 2015. This is in the interests of improving water usage efficiency in accordance with policy E7 of the Test Valley Borough Revised Local Plan 2016. This requirement can be provided for within a condition.

8.33 Subject to a condition in respect of water consumption at the property, to ensure compliance with TVBRLP policy E7 Water management, the proposal is considered to accord with this Policy.

8.34 Other matters

While noting that Houghton has been designated as a Neighbourhood Plan Area, a Neighbourhood Plan has not been adopted at this moment in time. Consequently no weight can be afforded to this matter in the determination of this application. Likewise, The Houghton Village Design Guide is in draft form, and has not been adopted. Consequently little weight can be afforded to this draft document.

9.0 CONCLUSION

9.1 The proposed dwelling is considered to represent an acceptable form of development for this site and accords with the relevant policies of the TVBRLP. The applicant has responded to the previously refused scheme by reducing the overall scale, massing and appearance of the dwelling and utilised 'visual' (roof heights, eaves height, materials etc) and 'physical' measures (recessing the 'extension' from the front face of the dwelling) to achieve this. The proposal is accompanied by details of proposed tree loss, and suitable replacement planting to maintain a visual, woodland contribution to the Houghton street scene following construction. Achieving these measures is important to not only to preserve the character and appearance of the Conservation Area, but also assist in integrating the new dwelling into the street scene. Subject to appropriate conditions securing both planting and long term maintenance of the wooded area the proposal preserves the character and appearance of the Conservation Area, and assists in preserving the setting of nearby Listed buildings.

9.2 The proposal is also acceptable with regard to highway safety, the amenity of nearby neighbours, and the amenity of future occupants of the dwelling, biodiversity matters, drainage and water supply, in accordance with the policies of the TVBRLP. The proposal is considered acceptable.

10.0 RECOMMENDATION

PERMISSION subject to:

1. The development hereby permitted shall be begun within three years from the date of this permission.
Reason: To comply with the provision of Section 91 of the Town and Country Planning Act 1990 as amended by Section 51 of the Planning and Compulsory Purchase Act 2004.
2. The development hereby permitted shall not be carried out except in complete accordance with the details shown on the submitted plans, numbers: 16/291/02 Rev. G; 16/291/03 Rev. H; 17347-BT7.
Reason: For the avoidance of doubt and in the interests of proper planning.
3. No development shall take place above DPC level of the development hereby permitted until samples and details of the materials to be used in the construction of all external surfaces hereby permitted have been submitted to and approved in writing by the Local Planning Authority. Development shall be carried out in accordance with the approved details.
Reason: To ensure the development has a satisfactory external appearance in the interest of visual amenities in accordance with Test Valley Borough Revised Local Plan (2016) Policy E1.
4. No development shall take place above DPC level of the development hereby permitted until Woodland Management Plan, and a schedule of implementation and maintenance for a minimum period of 20 years has been submitted to and approved in writing by the Local Planning Authority. The schedule shall include details of the arrangements for the phasing of the implementation and ongoing maintenance during that period in accordance with appropriate British Standards or other recognised codes of practise. Development shall be carried out in accordance with the approved schedule.
Reason: To ensure the provision, retention and maintenance to a suitable standard of approved woodland to maintain and enhance the appearance of the site and enhance the character of the development in the interest of visual amenity and to contribute to the character of the local area in accordance with Test Valley Borough Revised Local Plan (2016) Policy E2.
5. Before the development hereby permitted is commenced details, including plans and cross sections, shall be submitted to and approved by the Local Planning Authority of the existing and proposed ground levels of the development and the boundaries of the site and the height of the ground floor slab and damp proof course in relation thereto. Development shall be undertaken in accordance with the approved details.
Reason: To ensure satisfactory relationship between the new development and the adjacent buildings, amenity areas and trees in accordance with Test Valley Borough Revised Local Plan (2016) Policies E1 and E9.
6. The development hereby approved shall be designed and built to meet Regulation 36 2 (b) requirement of 110 litres/person/day water efficiency set out in part G2 of Building Regulations 2015.

Reason: In the interests of improving water usage efficiency in accordance with policy E7 of the Test Valley Borough Revised Local Plan 2016.

7. **At least the first 6 metres of the access track measured from the nearside edge of carriageway of the adjacent highway shall be surfaced in a non-migratory material prior to the use of the access commencing and retained as such at all times.**

Reason: In the interest of highway safety in accordance with Test Valley Borough Revised Local Plan (2016) Policy T1.

8. **Any gates shall be set back at least 6 metres from the edge of the carriageway of the adjoining highway and the access shall be splayed at an angle of 45 degrees from this point to the edge of the highway.**

Reason: In the interest of highway safety in accordance with Test Valley Borough Revised Local Plan (2016) Policy T1.

9. **Prior to the first occupation of the building hereby permitted, the car parking space(s), turning and manoeuvring area shall be constructed, surfaced and laid out in accordance with the approved plans. The area of land so provided shall be maintained at all times for this purpose.**

Reason: To ensure sufficient off-street parking has been provided and in the interest of highways safety in accordance with the Test Valley Revised Local Plan 2016 Policies T1 and T2.

10. **Prior to the commencement of development full details of the layout for the parking and manoeuvring on site of contractor's and delivery vehicles during the construction period shall be submitted to and approved in writing by the Local Planning Authority. The approved scheme shall be implemented prior to the commencement of development and retained for the duration of the construction period.**

Reason: In the interest of highway safety and in the interest of protecting Trees subject to a Woodland Preservation Order in accordance with Test Valley Borough Revised Local Plan (2016) Policies T1 and E2.

11. **Prior to the commencement of development the visibility splays, reference Plan 16/291/03 Rev. H shall be provided. Nothing within the approved visibility splays shall exceed 1 metre above the level of the adjacent carriageway (including the land level and any walls, fences and vegetation). Notwithstanding the provisions of the Town and Country Planning (General Permitted Development) Order 2015 (or any Order revoking and re-enacting that Order) these visibility splays shall be maintained in accordance with the above details at all times.**

Reason: In the interest of highway safety in accordance with Test Valley Borough Revised Local Plan (2016) Policy T1.

12. **Development shall proceed in accordance with the measures set out in section 6.1 'Mitigation' of the Ecological Assessment- Interim Report Land at Meadow View, Houghton' (Aluco Ecology, June 2018).**

Reason: To avoid impacts to protected and notable species and to conserve and enhance biodiversity in accordance with Policy E5 of the Test Valley Revised Local Plan DPD.

- 13 All works to existing trees, together with the provision of new tree planting, and new boundary hedging (including the new hedge along the road frontage of the dwelling) shall be carried out in accordance with the details contained in Drw.No.17347-BT7 (Barrell Tree Consulting) prior to first occupation of the dwelling hereby permitted.**
Reason: To ensure that only appropriate works to the trees identified on this plan are undertaken, and that suitable planting takes place on-site in a timely manner, to ensure an appropriate tree cover remains following construction of the new dwelling, to protect the character and appearance of the Conservation Area in accordance with Policy E9 of the Test Valley Borough revised Local plan (2016).
- 14. Prior to development taking place tree protective fencing shall be erected in accordance with the details contained in Drw.No.17347-BT7 (Barrell Tree Consulting), the “Arboricultural Assessment and Method Statement” (Ref: 17347-AA6-PB), and the report “Manual for Managing Trees on development sites” (Barrell Tree Consulting). The tree protective measures shall be retained on site for the full duration of the construction activity.**
Reason: To ensure that suitable tree protection has been erected prior to work being undertaken on site to minimise the chance of accidental damage to trees, and that appropriate tree cover remains following construction of the new dwelling, to protect the character and appearance of the Conservation Area in accordance with Policy E9 of the Test Valley Borough revised Local plan (2016).

Notes to applicant

- 1. In reaching this decision Test Valley Borough Council (TVBC) has had regard to the National Planning Policy Framework and takes a positive and proactive approach to development proposals focused on solutions. TVBC work with applicants and their agents in a positive and proactive manner offering a pre-application advice service and updating applicants/agents of issues that may arise in dealing with the application and where possible suggesting solutions.**
- 2 Birds' nests, when occupied or being built, and the widespread species of reptile receive legal protection under the Wildlife and Countryside Act 1981 (as amended). It is highly advisable to undertake clearance of potential bird nesting habitat (such as hedges, scrub, trees, suitable outbuildings etc.) outside the bird nesting season, which is generally seen as extending from March to the end of August, although may extend longer depending on local conditions. If there is absolutely no alternative to doing the work in during this period then a thorough, careful and quiet examination of the affected area must be carried out before clearance starts. If occupied nests are present then work must stop in that area, a suitable (approximately 5m) stand-off maintained, and clearance can only recommence once the nest becomes unoccupied of its own accord. Reptile habitat such as compost heaps should be carefully cleared by hand during warmer months as if hibernating**

reptiles are disturbed they will die. Any reptiles revealed should be moved to adjacent retained rougher / boundary habitat or allowed to move off of their own accord.

- 3. Bats and their roosts receive strict legal protection under the Wildlife and Countryside Act 1981 (as amended) and the Conservation of Habitats and Species Regulations 2017. All work must stop immediately if bats, or evidence of bat presence (e.g. droppings, bat carcasses or insect remains), are encountered at any point during this development. Should this occur, further advice should be sought from Natural England and/or a professional ecologist.**
-

APPENDIX B

Officer Update Report to Southern Area Planning Committee on 9 October 2018

APPLICATION NO.	18/01953/FULLS
SITE	Land adjacent to Meadow View, Houghton, Stockbridge, SO20 6LT, HOUGHTON
COMMITTEE DATE	9 October 2018
ITEM NO.	8
PAGE NO.	35 - 58

1.0 CONSULTATIONS/REPRESENTATIONS

1.1 Houghton Parish Council. Objection (Summarised)

- The copse is part of an ambitious five year programme of work by the British Trust for ornithology – to improve knowledge & understanding of breeding owl species.
- Owls are thought to breed here.
- The village Rookery is on site too.
- Migrant birds, many on the red list, are observed in the copse. The River Test is ideal as one of the green corridors for migrating birds, with its small sheltered woods and copses.
- Houghton is a small conservation village which has lost 3 vital habitats in recent years, and seen unprecedented development over the last two years, with 13 houses built within the next year, 6 already in Kents Orchard, potential replacement of Dianthus, works to South End Cottage and Houghton Farmhouse with a disastrous effect on bio diversity.
- This is its last remaining copse. Its native trees and bushes make it an excellent bio-diverse habitat, with an understorey perfect for foraging ground feeding birds, animals and insects which must be preserved as part of the 'bigger conservation picture'.
- The whole wood tree preservation order is of huge benefit to conservation and biodiversity in Houghton and beyond.
- The village requests this is retained in perpetuity.
- The proposal almost certainly contravenes the Conservation of habitats and Species Regs, 2010.
- The ecologists report failed to take this cumulative impact into account, as did the HCC Ecologists response.
- Loss of biodiversity recently included the mistaken removal of an ancient hedgerow. Trees were lost at the Kents Orchard development.
- There is no current proposal for a garage or outbuildings which would further impact on the biodiversity of the copse.
- The Parish Council has never seen so many objections to an application, which indicates how important the copse is to the village.

1.2 **Tree Officer** – No objection (Summarised)

Satisfied that the Arboricultural Reports Barrell Tree Care Report address the arboricultural aspects of this case as thoroughly as can be.

Please seek removal of PD rights and ensure that an informative is attached to any consent.

2.0 **PLANNING CONSIDERATIONS**

2.1 The Parish Council's additional response is clear. The HCC Ecologist has however, clearly stated that the submitted Ecology Report contained all Survey information required, including a mitigation section, to mitigate the impact of the development on ecological interests. These are included in the proposed conditions.

2.2 Conditions have been recommended that secure the planting and future management of the woodland, which has hitherto been absent.

2.3 The representation made does not therefore alter the officer's recommendation.

2.4 With reference to the Tree Officer additional response, paragraph 206 of the National Planning Policy Framework states Planning conditions should only be imposed where they are:

1. necessary;
2. relevant to planning and;
3. to the development to be permitted;
4. enforceable;
5. precise and;
6. reasonable in all other respects.

In this circumstance the blanket removal of permitted development rights would not be necessary and would be considered unreasonable as the removal of any tree within the site would require the formal consent of the Council. To undertake works to a preserved tree without first obtaining consent can result in criminal prosecution. Secondly, no evidence has been advanced to demonstrate that works which would constitute permitted development would result in harm to any protected trees. As such, it is the view of officers that such a condition should not be added to the decision should permission be granted.

2.5 Point of clarification

Pages 57-58 comprise Appendix A, the plans and elevations for the refused scheme 17/02017/FULLS.


3.0 **RECOMMENDATION**

PERMISSION subject to conditions and notes as per agenda report recommendation and additional Note no. 4.

Notes 1-3 and note 4.

4. The various trees standing within this site are all protected by virtue of standing within the Houghton Conservation Area and also by Tree Preservation Order (TPO.TVBC.1124) Damage to any of the trees not identified for removal on the approved plans is an offence. Failure to

comply in full with Barrell Tree Consultancy Arboricultural Assessment and Method Statement 17347-AA2-PB is likely to result in damage to the trees. Damage to the trees may lead to the prosecution of those undertaking the work and also of those instructing, causing or permitting the works.



Siteplan

Test Valley
Borough Council

REV	DESCRIPTION	DATE	AUTH
-	Issued for client approval	181116	LR
A	Issued for client approval	071216	LR
B	Issued for client approval	131216	LR
C	Issued for pre-planning	211216	LR
D	Issued for client approval	090317	LR
E	Issued for client approval	020617	LR
F	Issued for pre-planning	020817	LR
G	Issued for planning	240718	LR

Do not scale from drawing, use figured dimensions only. Subject to site survey and all necessary comments. All dimensions to be checked by the architect before work commences. Errors or omissions to be reported to the client immediately. This drawing is to be read in conjunction with other relevant materials.

LUKE ROSE ARCHITECT
 Beck Cottage, Abbots Ann
 Hampshire SP7 1NW
 t: 01753 834444
 e: info@luke-rose.co.uk
 www.luke-rose.co.uk

PLANNING

Architecture | Construction | Design | Development

JOB
 Meadow House
 South End
 Houghton
 SO20 6LT

TITLE
 Proposed plans, site and location plan

SCALE
 1:100






DATE
 Jul 18

AUTHOR
 LR

DRAWING NO
 16/291/02

REV
 G

Location plan
 scale 1:2500



Scale
 In Meters at 1:200



Site plan 1:200

Do not scale from drawings, use figured dimensions only. Subject to site survey and all necessary consents. All dimensions to be checked by user and any discrepancies, errors or omissions to be reported to the Architect before work commences. This drawing is to be read in conjunction with other relevant materials.

REV	DESCRIPTION	DATE	AUTH
-	Issued for client approval	18/11/16	LR
A	Issued for client approval	07/12/16	LR
B	Issued for client approval	13/12/16	LR
C	Issued for pre-planning	21/12/16	LR
D	Issued for client approval	07/03/17	LR
E	Issued for client approval	28/03/17	LR
F	Issued for client approval	02/08/17	LR
G	Issued for Planning	09/02/18	LR
H	Issued for Planning	24/07/18	LR

DRAWING ISSUE: Planning

LUKE ROSE ARCHITECT
 Beck Cottage, Abbots Ann
 Hampshire SP7 7JW
 t: 01753 630000
 e: info@lukerose.co.uk
 www.lukerose.co.uk







Architecture | Construction | Design | Development

JOB: Meadow House South End Houghton SO20 6LT

TITLE: Proposed elevations, vehicle and pedestrian gate detail

SCALE: 1:100 DATE: Jul18 AUTHOR: LR

DRAWING NO: 16/291/03 REV: H



Tree schedule

Tree No	Species	Category	RPA Radius	Tree Works
All retained hedgerows				
T601	Yew	C	4.2	Carry out safety check and lift over site to 3.4m as necessary.
T602	Ash	B	10.2	-
T603	Ash	B	6.3	-
T604	Ash	A	13.8	-
T605	Blackthorn	C	6.3	-
T606	Ash	C	1.8	-
T607	Ash	C	5.1	-
T608	Ash	C	4.8	-
T609	Ash	B	6.9	Fell for development
T610	Ash	C	3.6	Fell for development
T611	Elder	C	3.0	Fell for development
T612	Ash	C	3.6	Consent already extant for removal
T613	Ash	C	5.1	Fell for development
T614	Ash	C	2.4	Fell for development
T615	Laurel	C	4.8	Consent already extant for removal
T616	Hawthorn	C	2.7	-
T617	Ash	C	4.2	-
T618	Ash	U	3.6	Fell for prudent management
H619	Ash, hawthorn, elder	C	3.0	Reductive management to restore hedgerow form - reduce existing elements to post points of pruning (2m above ground level)
T620	Yew	B	6.0	-
T621	Hawthorn	C	1.5	-
T622	Yew	C	1.8	-
T623	Yew	C	1.5	-
T624	Hazel	B	6.6	-
T625	Hazel	C	3.0	Coppice to ground level
T626	Hazel	B	6.6	Coppice to ground level
T627	Ash	C	2.7	-
G628	Ash, cherry	U	2.4	-
T629	Ash	C	7.8	Consent already extant for removal
T630	Cherry	C	3.0	-
T631	Ash	B	11.1	-
T632	Hazel	C	3.0	Coppice to ground level
T633	Ash	B	3.3	-
T634	Cherry	C	2.4	-
G635	Hazel	C	3.6	-
T636	Cherry	C	1.8	-
T637	Cherry	C	2.4	-
T638	Ash	C	4.8	-
T639	Ash	C	2.4	-
T640	Apple	C	2.7	-
T641	Hazel	C	3.0	-
T642	Spindle tree	C	3.0	-
T643	Ash	C	3.0	-
T644	Ash	B	3.6	-
T645	Willow	C	8.4	Fell for development
T646	Willow	C	7.2	Consent already extant for removal
T647	Ash	B	6.6	-
T648	Cherry	C	3.0	Fell for development
T649	Ash	C	3.6	Fell for development
T650	Cherry	C	3.0	Fell for development
T651	Elder	C	4.8	Fell for development
G652	Cherry	U	2.4	Fell for prudent management
T653	Ash	C	6.0	-
T654	Ash	C	2.4	-
T655	Ash	C	2.4	-
T656	Ash	C	4.8	-
T657	Ash	C	3.0	-
G658	Beech	C	1.5	-
T659	Ash	C	1.8	Fell for development
T660	Ash	B	13.2	Crown reduction by a maximum of 7m to establish canopy height of no less than 14m from ground level
T661	Ash	B	8.1	Crown reduction by a maximum of 7m to establish canopy height of no less than 14m from ground level
T662	Ash	B	14.1	Fell for development
T663	Yew	B	8.1	Fell for development
T664	Ash	U	7.8	Fell for prudent management

Page 42

Tree protection plan

Location of trees, tree protection proposals at Meadow View, (land adjacent), Houghton, Stockbridge

Barrell Plan Ref: 17347-817

Provided Plan Refs: ENC071116-204 & 162910Z Rev G

barrell THE CONSUJANT

www.barrelltreecare.co.uk

Permission is granted to scale from this drawing for Local Authority Planning Approval purposes only. This drawing is the property of Barrell Tree Care and its use for any other purpose without the written consent of Barrell Tree Care is prohibited. This drawing to be used in conjunction with the Barrell Tree Care site visit report and any other documents provided to the client. This drawing to be reproduced in colour only.



SGN No	Category	Always:
SGN 1	Monitoring tree protection	<ul style="list-style-type: none"> have a pre-commencement meeting with the tree consultant before work commences use the tree consultant to regularly check that protection remains fit for purpose use the tree consultant to supervise work in RPAs keep a written record of supervision
SGN 2	Fencing protected trees	<ul style="list-style-type: none"> install protection before development commences make sure protection is fit for purpose, i.e. it prevents damage to trees keep protection in place until there is no risk to trees get written permission to move or remove any protection
SGN 3	Ground protection	<ul style="list-style-type: none"> install protection before development commences make sure protection is fit for purpose, i.e. it prevents damage to trees keep protection in place until there is no risk to trees get written permission to move or remove any protection
SGN 4	Pollution control	<ul style="list-style-type: none"> keep toxic products away from RPAs
SGN 6	Height restrictions	<ul style="list-style-type: none"> prevent the access of vehicles into controlled areas taller than the critical height
SGN 9	Installing/upgrading surfacing in RPAs	<ul style="list-style-type: none"> use the tree consultant to supervise work in RPAs minimise damage to roots and soil minimise excavation when installing or upgrading surfacing in RPAs
SGN 11	Installing services in RPAs	<ul style="list-style-type: none"> use the tree consultant to supervise work in RPAs select the least damaging option for trenching, over broken trench over continuous trench use trench shields if trenchless is not feasible
SGN 12	Landscaping in RPAs	<ul style="list-style-type: none"> use the tree consultant to supervise work in RPAs use plants of like species with 3m of the trunks of retained trees

How to use plan

More detailed guidance on each Site Guidance Note (SGN) can be found in a printed hard copy compilation of all the SGNs, issued to the Site Manager at the pre-commencement site meeting. The SGNs are also available on the Barrell Tree Care website. The SGNs are also available on the Barrell Tree Care website. The SGNs are also available on the Barrell Tree Care website.

- clicking the image links in the electronic pdf version of this plan;
- holding a mobile phone QR (Quick Response) code reader over the QR code in the paper version of this plan;
- visiting our website at <https://www.barrelltreecare.co.uk/resources/technical-guidance>

Do not scale from drawings, use figured dimensions only. Subject to all survey and all necessary consents. All dimensions to be checked by the user and any discrepancies, errors or omissions to be reported to the Architect before work commences. This drawing is to be read in conjunction with other relevant materials.

REV	DESCRIPTION	DATE	AUTH
-	Issued for client approval	18/11/16	LR
A	Issued for client approval	13/12/16	LR
A	Issued for pre-planning	21/12/16	LR
A	Issued for client approval	07/03/17	LR
A	Issued for planning	02/08/17	LR
A	Issued for planning	24/07/18	LR

DRAWING ISSUE Planning

LUKE ROSE ARCHITECT
Beck Cottage, Abbots Ann
Hampshire SP11 7NW
Tel: 01264 710165
email: l.rose@luke-rose.co.uk
www.luke-rose.co.uk


RIBA
Architecture | Construction | Design | Development

JOB
Meadow House
South End
Houghton
SO20 6LT


TITLE
Existing site plan location
plan and photos

SCALE 1:200
DATE Jul18
AUTHOR LR


DRAWING NO 16/291/01
REV A




Site pictures




APPENDIX A - REFUSED SCHEME 17/02017/FULLS




Location plan 1:1250




Site plan 1:500




Roof plan



Basement floor



Ground floor



First floor

REV	DESCRIPTION	DATE	AUTH
-	Issued for client approval	18/11/16	LR
A	Issued for client approval	07/12/16	LR
B	Issued for client approval	13/12/16	LR
C	Issued for pre-planning	21/12/16	LR
D	Issued for client approval	07/03/17	LR
E	Issued for client approval	08/03/17	LR
F	Issued for client approval	20/03/17	LR
G	Issued for planning	09/03/17	LR


Do not scale from drawings, use figured dimensions only. Subject to site survey and all necessary consents. All dimensions to be checked by user and any discrepancies, errors or omissions to be reported to the Architect before work commences. This drawing is to be read in conjunction with other relevant materials.

DRAWING ISSUE	Planning
JOB	Meadow House South End Houghton SO20 6LT
TITLE	Proposed plans site plan and location plan
SCALE	1:100
DATE	Aug 17
AUTHOR	LR
DRAWING NO	16/291/02
REV	G

APPENDIX 1 - REFUSED SCHEME ELEVATIONS
17/02017/FULLS


REV	DESCRIPTION	DATE	AUTH
-	Issued for client approval	18/11/16	LR
A	Issued for client approval	07/12/16	LR
B	Issued for client approval	13/12/16	LR
C	Issued for pre-planning	21/12/16	LR
D	Issued for client approval	07/03/17	LR
E	Issued for client approval	09/03/17	LR
F	Issued for client approval	02/04/17	LR

Do not scale from drawing, use figured dimensions only. Subject to site survey and all necessary consents. All dimensions to be checked by Architect before work commences. This drawing is to be read in conjunction with other relevant materials.




North elevation

South elevation




East elevation

West elevation



DRAWING ISSUE	Planning
	LUKE ROSE ARCHITECT
JOB	Meadow House South End Houghton SO20 6LT
TITLE	Proposed elevations and splay lines
SCALE	1:100
DATE	Aug 17
AUTHOR	LR
DRAWING NO	16/291/03
REV	F


Anticipated onsite canopy cover in 2038/2039



Projected % canopy cover in 20 years


- The above canopy projection assumes:
- No proactive tree management.
 - Significant decline in the onsite ash (*Fraxinus* sp) population due to Chalara dieback (caused by fungal pathogen *Hymenoscyphus fraxineus*).
 - Scrub/laurel/bramble levels to significantly increase and compromise understory vitality and natural regeneration.

Extract of BT7 Tree protection plan



- Anticipated 20 year growth dimensions (metres) of new proposed new tree planting:
- Type 1 – Yew – 7m high with 5m canopy diameter (180% increase from size at planting)
 - Type 2 – Crab apple – 6m high with 4m canopy diameter (140% increase from size at planting)
 - Type 3 – Field maple– 10m high with 7m canopy diameter (233% increase from size at planting)
 - Type 4 – Lime – 10m high with 6m canopy diameter (300% increase from size at planting)
 - Type 5 – Wild cherry – 12m high with 7m canopy diameter (380% increase from size at planting)

Anticipated onsite canopy cover in 2038/2039
with residential dwelling



Projected % canopy cover in 20 years with residential dwelling

- The above canopy projection assumes:
- Protective tree management by future occupier in conjunction with the 20 year woodland management plan.
 - Any tree losses arising from Chalara will be replaced with new trees by the occupier in line with the species selection mix set out in the woodland management plan.
 - Reduction and control of inappropriate tree species leading to understory enhancement (specifically in the western site extents) providing onward natural regeneration.