



Proposed new stairs  
 down to basement level →

MISSING CAST IRON COLUMN TO BE REINSTATED  
 EXISTING DOOR & FRAME TO BE LOWERED TO EX. G.F.L.  
 PROPOSED FLIGHT OF STEPS / JUNKEN ENTRANCE TO LOWERED POOR.  
 SNOOKER TABLE RELOCATED.  
 REMOVE EXISTING CRADE CONCRETE STEPS

EXISTING STAIRS RETAINED.

EXTENT OF EXISTING SAND & CEMENT FILL TO BE REMOVED DOWN TO EXISTING CONCRETE OVERSITE SLAB.

BOWLED WALLING TO SOUTHERN END OF WEST ELEVATION TO BE STABILISED IN ACCORDANCE WITH STRUCTURAL ENGINEERS' REQUIREMENTS/DETAILS.

INSULATED DRY-LINING TO IMPROVE 'U' VALUE TO BUILDING / REDUCE HEAT LOSS (SUSTAINABILITY)

BOWED BRICK ARCH TO BE STABILISED IN ACCORDANCE WITH STRUCTURAL ENGINEERS' REQUIREMENTS/DETAILS.

GROUND FLOOR

0 5m.

SECTIONAL COVERS FOR SNOOKER TABLE FOR USE AS FOOD SERVERY.

OIL-FIRED BOILER.

PROPOSED OPENING TO ACCOMMODATE POOR.

BULKHEAD TO ALLOW FOR LOWERED FLOOR / TO NARROW STEPS ABOVE.

PROPOSED STEPS OVER CLAD IN TRADITIONAL BEAD & BUTT BOARDING (PAINTED)

Proposed conservation rooflight over

NOTE:

OTHER THAN STRUCTURAL WORKS TO S.E CORNER OF STABLE 2 / ACCOMMODATION OF PROPOSED STEPS TO 1ST FLOOR OVER (FROM MAIN BARN) NO WORKS OTHER THAN REDECORATION.

SUBSIDIENCE ISSUES TO BE ADDRESSED IN ACCORDANCE WITH STRUCTURAL ENGINEERS' DETAILS.

Rev B - Planning Application 19/03/20

Rev A - Proposed window to WC omitted / Rooflight added

DWG. NO. 18/3158/2018

PROPOSED ALTERATIONS TO APPLSHAW BARN, APPLSHAW, ANDOVER, GROUND FLOOR PLAN. SCALE: 1:1000 A3 @ R.P.L. MAR 19